

Contents

1.0	INTRODUCTION	29
1.1	Why This Book?	29
2.0	LANDFILL BASICS	31
2.1	Why Do We Have Sanitary Landfills?	32
2.1.1	Environmental Protection	32
2.1.1.1	Groundwater Protection	33
2.1.1.2	Surface Water Protection	33
2.1.1.3	Air Quality	34
2.1.1.4	Litter Control	34
2.1.1.5	Vector Control	35
2.1.2	Least Cost Alternative	35
2.2	Landfill Operator's Responsibility	35
2.3	Landfill Statistics	36
2.4	Toeing the Regulatory Mark	37
2.4.1	Federal Regulations - Subtitle D	38
2.4.2	State Regulations	38
2.4.3	Local Regulations	38
3.0	LANDFILL SITING	39
3.1	Phasing the Search	40
3.1.1	Phase 1 — Preliminary Screening	40
3.1.2	Phase 2 — Short Listing the Sites	41
3.1.2.1	Ownership/Acquisition	41
3.1.2.2	Zoning	41
3.1.2.3	Road Access	42
3.1.2.4	Topography	42
3.1.2.5	Site Capacity	42
3.1.2.6	Soils	42
3.1.2.7	Depth to Groundwater	43
3.1.2.8	Proximity to Wells	43
3.1.2.9	Surface Water	44
3.1.2.10	Flood Hazard	44
3.1.2.11	Airport Safety	44
3.1.2.12	Holocene Fault	44
3.1.2.13	Seismic Impact Zone	45
3.1.2.14	Site Stability	45
3.1.2.15	Run-on/Runoff Controls	46
3.1.2.16	Landfill Gas Control	46
3.1.2.17	Land Use	46
3.1.2.18	Agricultural Land	47
3.1.2.19	Habitat Value	47
3.1.2.20	Visual Impacts	47
3.1.2.21	Downwind Impacts	47
3.1.2.22	Landfill Site Ranking	47

3.2	Economic Comparison	49
3.2.1	Land Costs	49
3.2.2	Permitting and Design Costs	49
3.2.2.1	Communication with Regulators	49
3.2.2.2	Public Involvement and Support	49
3.2.2.3	Phasing the Site Investigation	50
3.2.2.4	Maintain Design Team Interaction	50
3.2.2.5	Use an Accepted, Proven Design	50
3.2.3	Construction Costs	50
3.2.4	Operating Costs	51
3.2.5	Closure Costs	51
3.2.5.1	Cap Design	51
3.2.5.2	Closure Schedule	51
3.2.6	Post-Closure Costs	52
3.2.7	Tariffs or Special Fees	52
3.2.8	Hauling Costs	52
3.3	Public Participation	54
4.0	CHARACTERIZING YOUR LANDFILL	55
4.1	Understanding the Constraints of Your Site	55
4.1.1	Political Constraints	55
4.1.2	Environmental Constraints	55
4.1.3	Regulatory Constraints	55
4.1.4	Financial Constraints	56
4.2	Climate	56
4.2.1	Precipitation (Rain or Snow)	57
4.2.2	Evaporation and Evapotranspiration	57
4.2.3	Temperature/Seasonal Variations/Extremes	57
4.2.4	Wind Conditions	58
4.3	Topography	58
4.4	Soil Conditions	59
4.4.1	Soil Types	59
4.4.1.1	Clay	59
4.4.1.2	Silt	59
4.4.1.3	Sand	60
4.4.1.4	Gravel	60
4.4.2	Unified Soil Classification System	60
4.4.3	Gradation	60
4.4.4	Moisture Content (M.C.)	62
4.4.5	Permeability	63
4.4.6	Density	64
4.4.7	Predicting Soil Type by Drainage Pattern	65
4.5	Groundwater Conditions	66
4.5.1	Groundwater Mounding	66
4.5.2	Groundwater Divide	66
4.5.3	Confining Layers	67
4.6	Waste Stream Description	68
4.6.1	Class of Waste	68
4.6.1.1	Unacceptable Wastes	68
4.6.1.2	Special Wastes	68

4.6.1.3	Acceptable Wastes	68
4.6.1.4	Municipal Solid Waste	68
4.6.1.4.1	Demolition Waste	68
4.6.1.4.2	Green Waste	69
4.6.2	Method of Delivery	69
4.6.2.1	Route Trucks	69
4.6.2.2	Roll-Off Trucks	70
4.6.2.3	Transfer Trucks	70
4.6.2.3.1	Loading Methods	71
4.6.2.3.2	Unloading Methods	71
4.6.2.4	Contractors	71
4.6.2.5	Public (Self-haul)	71
4.7	Quantifying the Waste Stream	72
4.7.1	Tonnage	72
4.7.1.1	Annual Tonnage	72
4.7.1.2	Seasonal Tonnage	73
4.7.1.3	Daily Tonnage	73
4.7.1.4	Hourly Tonnage	73
4.7.2	Yardage	75
4.7.2.1	Annual Yardage	75
4.7.2.2	Seasonal Yardage	75
4.7.2.3	Daily Yardage	75
4.7.2.4	Hourly Yardage	75
4.7.3	Vehicle Count	76
4.7.3.1	Annual Vehicle Count	76
4.7.3.2	Daily Vehicle Count	76
4.7.3.3	Hourly Vehicle Count	76
4.7.3.3.1	Vehicle Stacking Distance	77
4.7.3.3.2	Number of Collectors	78
4.7.3.3.3	Number of Spotters	78
4.7.3.4	15 Minute Vehicle Count	79
5.0	LANDFILL DESIGN	81
5.1	How Sanitary Landfills Work	81
5.2	Check Your Footprint - The First Step	82
5.2.1	Establishing the Limit of Refuse Filling	82
5.2.2	Balancing the Site	83
5.2.2.1	Size of Waste Stream	83
5.2.2.2	Type of Garbage	83
5.2.2.3	Type of Soil	83
5.2.2.4	Refuse Density	83
5.2.3	Establishing the Base Grades	84
5.2.3.1	Elevation	84
5.2.3.2	Base Grade Slope	84
5.2.3.3	Slope Direction	84
5.2.3.4	Depth to Groundwater	85
5.2.3.5	Soil Type	85
5.2.3.6	Cost of Excavating	85
5.2.3.7	Consolidation Due to Surcharging	86
5.2.3.8	Volume of Soil Required	87

5.2.3.9	Surface Drainage	87
5.2.3.10	Selection of Liner & LCS	88
5.2.3.10.1	Type of System	88
5.2.3.10.2	Materials	88
5.2.3.10.3	Simplicity	88
5.2.3.10.4	Regulatory Acceptance	89
5.2.3.11	Stability	89
5.2.3.12	Site Design Life	91
5.2.3.13	Time Value of Money	91
5.2.4	Establishing the Final Grades	92
5.2.4.1	Aesthetics	92
5.2.4.2	Regulatory Limits	93
5.2.4.3	Stability	93
5.2.4.4	Drainage	93
5.2.4.5	Settlement	93
5.2.4.5.1	Ultimate Settlement	94
5.2.4.5.2	Drainage Problems	95
5.2.4.6	End Use	96
5.2.4.6.1	Rural Areas	96
5.2.4.6.2	Urban Areas	96
5.2.4.7	Cap Design	96
5.3	Accessibility	96
5.4	Liner Systems	97
5.4.1	Liner Regulations	97
5.4.1.1	Design Standard	97
5.4.1.2	Performance Standard	98
5.4.2	Liner Types	98
5.4.2.1	Native Clay Liner	98
5.4.2.2	Composite Liners	99
5.4.2.3	Double-Composite Liners	99
5.5	Leachate Collection Systems	99
5.5.1	HELP Modeling	99
5.5.2	Drainage Layer	100
5.5.2.1	Dendritic System	100
5.5.2.2	Blanket-type System	100
5.5.2.3	Leachate Transmission	101
5.6	Landfill Gas	101
5.6.1	Landfill Gas Production	101
5.6.2	Landfill Gas Control	102
5.7	Cover Soil Systems	104
5.7.1	Daily Cover	104
5.7.2	Alternative Daily Cover	104
5.7.3	Intermediate Cover	104
5.7.4	Final Cover	105
5.7.4.1	Base Layer	105
5.7.4.2	Gas Transmission Layer	105
5.7.4.3	Composite Layer	106
5.7.4.4	Drainage Layer	106
5.7.4.5	Topsoil Layer	106

5.8	Precipitation and Drainage Controls	106
5.8.1	Run-on Controls	106
5.8.2	Runoff Controls	107
5.8.3	Minimizing Infiltration By Use of Snow Drift Control	108
5.8.4	Surface Drainage - The Basics	110
5.8.5	Designing Drainage Structures	110
5.9	Site Closure/Post-Closure	111
5.9.1	Closure Phasing	111
5.9.2	Post-Closure Maintenance Plan	111
6.0	LANDFILL EQUIPMENT	115
6.1	Equipment Types	115
6.1.1	Dozer	115
6.1.2	Landfill Compactor	116
6.1.3	Track Loaders	116
6.1.4	Backhoe	116
6.1.5	Water Truck	117
6.1.6	Scraper	117
6.1.7	Motor Grader	117
6.1.8	Wheel-Loaders	118
6.2	Choosing the Correct Equipment	118
6.2.1	Basic Task-Based Method	119
6.2.1.1	Define the Tasks	120
6.2.1.2	Match Equipment to Each Task	120
6.2.1.3	Assign Equipment Costs	120
6.2.1.4	Consider Alternative Machines	120
6.2.2	Comprehensive Task-Based Method	121
6.2.2.1	Getting Started	121
6.2.2.2	Dozer Selection	122
6.2.2.2.1	Determining Push Distance	122
6.2.2.2.2	Annual Pushing Cost	123
6.2.2.2.3	Support Work Cost	123
6.2.2.2.4	Total Annual Cost	124
6.2.2.2.5	Summary of Dozer Selection Analysis	124
6.2.2.3	Scraper Selection	124
6.2.2.3.1	Define a Course	125
6.2.2.3.2	Select Scrapers	125
6.2.2.3.3	Run Simulation	125
6.2.2.4	Compactor Selection	125
6.2.2.4.1	Productivity	126
6.2.2.4.1.1	Varying Machine Cost Per Hour	126
6.2.2.4.1.2	Site Life	126
6.2.2.4.1.3	Net Present Value	126
6.2.3	Look-up Tables	127
6.2.4	Equipment Versatility	127
6.3	Rent, Lease, or Buy?	129
6.3.1	Rent	129
6.3.1.1	Pros	129
6.3.1.2	Cons	129
6.3.2	Buy	130

6.3.2.1	Pros	130
6.3.2.2	Cons	130
6.3.3	Lease	130
6.3.3.1	Pros	130
6.3.3.2	Cons	131
6.4	Ways to Cut Equipment Costs	131
6.4.1	Reducing Out-of-Pocket Costs	131
6.4.2	Reducing Hidden Costs	133
6.4.2.1	Unproductive Machine	133
6.4.2.2	Downtime	133
6.4.2.2.1	Major Rebuild (Engine, Transmission, etc.)	134
6.4.2.2.2	Unexpected Breakdown	134
6.4.2.2.3	No Operator Available	134
6.4.2.2.4	Machine Down Due to Lack of Support Equipment	134
6.4.2.2.5	Machine Down for Service	135
6.4.2.3	Wrong Machine for the Job	135
6.5	Basics of Equipment Operation	136
6.5.1	Mounting and Dismounting	136
6.5.2	Parking the Machine	136
6.5.3	Safety	136
6.6	Maintenance	137
6.6.1	Dust	138
6.6.2	High Temperatures	139
6.6.3	Blowing Litter	140
6.6.4	Garbage	140
6.6.5	Walk-Around Inspection	141
6.7	Repair vs. Replacement	141
6.7.1	Owning Costs	142
6.7.1.1	Salvage Value	142
6.7.2	Operating Costs	142
6.7.2.1	Productivity	143
6.7.2.2	Downtime	143
6.7.2.3	Total Cost	144
6.8	Owning & Operating (O&O) Costs	145
6.8.1	Calculating Undercarriage Costs	147
7.0	LANDFILL OPERATIONS	151
7.1	The Basics	151
7.1.1	Daily Landfill Operations	151
7.1.2	Teamwork is Key	151
7.1.2.1	Spotter	151
7.1.2.2	Dozer	152
7.1.2.3	Compactor	152
7.1.2.4	Scraper	152
7.2	Fill Sequencing Plans - How to Read & Understand Them	152
7.2.1	North Arrow	153
7.2.2	Scale	153
7.2.3	Legend	154
7.2.4	Notes	154
7.2.5	Volume Calculations	154

7.2.6	Slope	154
7.2.7	Access Roads	156
7.2.8	Drainage	156
7.2.9	Limit Lines	156
7.2.10	Coordinates	156
7.2.11	Details	157
7.2.12	Type of Plans	158
7.2.12.1	Landfill Development Plan	158
7.2.12.2	Site Drainage Plan	159
7.2.12.3	Landfill Base Grade Plan	159
7.2.12.4	Landfill Final Grade Plan	159
7.2.12.5	Fill Sequence Plans	159
7.3	Fill Sequencing Costs	160
7.4	Fill Sequencing	161
7.4.1	Sizing the Individual Phases	161
7.4.1.1	Economy of Scale	161
7.4.1.2	Time Value of Money	162
7.4.2	Sequencing the Phases	162
7.4.2.1	Aesthetics	162
7.4.2.2	Access	162
7.4.2.3	Drainage	163
7.4.2.4	Leachate Control	163
7.4.2.5	Soil Handling	163
7.4.3	Excavation Plans	163
7.4.3.1	Sequencing The Excavation	164
7.4.3.1.1	Equipment Cost/Hour	165
7.4.3.1.2	Haul Road Slope	165
7.4.3.1.3	Annual Soil Requirements	165
7.4.3.1.4	Depth of Individual Excavation Cells	165
7.4.3.1.5	Incremental Distance for Calculating Cost	166
7.4.4	Closure Sequencing	166
7.4.4.1	Economics	166
7.4.4.2	Leachate Minimization	167
7.4.4.3	Drainage	167
7.5	Getting Garbage to the Face	167
7.5.1	Traffic Management	167
7.5.1.1	Access Road Placement	167
7.5.1.2	Access Road Design	168
7.5.1.3	Signs	168
7.5.1.4	Spotters	168
7.5.1.5	Speed Limits	168
7.5.1.6	Vehicle Segregation	168
7.5.2	Pre-Measurement of Loads	169
7.5.3	Transfer Truck Schedule	169
7.5.4	Working Safely Around Public Vehicles	173
7.5.5	Spotter's Responsibility - Keeping the Operation in Order	173
7.5.5.1	Load Identification and Placement	174
7.5.5.1.1	Type of Delivery Vehicle	174
7.5.5.1.2	Type of Garbage	174

	7.5.5.1.3	Size of the Load	174
	7.5.5.1.4	Potential to Create Litter	175
	7.5.5.1.5	Vehicle Unloading Time	175
	7.5.5.1.6	Is the Load Obnoxious or Potentially Dangerous? ...	176
	7.5.5.1.7	How Busy is the Landfill?	176
	7.5.5.1.7.1	Time of Day	177
	7.5.5.1.7.2	The Amount of Waste Already Stacked	177
	7.5.5.1.7.3	Type of Cell Being Constructed	178
	7.5.5.1.7.4	Weather Conditions	178
	7.5.5.1.8	Type of Garbage	178
7.5.6	Pushing to the Face		178
7.5.6.1	Pushing Behind Tippers		178
7.5.6.2	Packer Truck Loads		180
	7.5.6.2.1	Density	180
	7.5.6.2.2	Cohesiveness	180
	7.5.6.2.3	Type of Garbage	181
	7.5.6.2.4	Unloading Time	181
7.5.6.3	Public Loads		182
7.5.7	When and How to Push to the Face		182
7.5.7.1	The Dozer's Role in Cell Building		183
7.5.7.2	What is the Optimum Push Distance?		183
	7.5.7.2.1	Pad Costs	183
	7.5.7.2.2	Pushing Costs	183
7.5.7.3	Recognizing Different Waste Types		184
7.5.7.4	Dry Weather Operations (Pushing Short)		184
	7.5.7.4.1	Reduced Litter	184
	7.5.7.4.2	Safer Vehicle Access	184
	7.5.7.4.3	Reduced Equipment Costs	185
	7.5.7.4.4	Minimize Soil Use	185
7.5.7.5	Wet-Weather Operations (Pushing From a Tipping Pad)		185
	7.5.7.5.1	Tipping Pad Capacity	185
	7.5.7.5.2	Tipping Pad Drainage	186
	7.5.7.5.3	Types of Wet-Weather Pads	187
	7.5.7.5.3.1	Conventional Tipping Pad	187
	7.5.7.5.3.2	Rubble-edged Tipping Pad	187
	7.5.7.5.3.3	Radial Tipping Pad	188
	7.5.7.5.3.4	Elevated Radial Tipping Pad	188
	7.5.7.5.4	Temporary Soil Stockpiles	189
7.6	Cell Construction		190
7.6.1	The Compactor's Role in Cell Building		190
	7.6.1.1	Cell Placement	190
7.6.2	Cell Geometry		190
	7.6.2.1	Cell Width	191
	7.6.2.2	Cell Depth	192
	7.6.2.3	Cell Advance	192
	7.6.2.4	Surface Area	192
7.6.3	Types of Cell Construction		193
	7.6.3.1	Build From the Bottom	193
	7.6.3.2	Build From the Top	193

	7.6.3.3	Build in Horizontal Lifts	194
	7.6.3.4	Build in Sloping Lifts	194
7.6.4		Spreading Refuse	194
7.6.5		Compacting Refuse	195
	7.6.5.1	Factors Affecting Compaction	195
	7.6.5.1.1	Weight of Compactor	195
	7.6.5.1.2	Speed of Compactor	196
	7.6.5.1.3	Lift Thickness	197
	7.6.5.1.4	Design of Compactor (Wheels and Teeth)	197
	7.6.5.1.4.1	Wheel Diameter	197
	7.6.5.1.4.2	Wheel Width	197
	7.6.5.1.4.3	Tooth Design	198
	7.6.5.1.4.4	Tooth Pattern	198
	7.6.5.1.4.5	Overall Cost of Wheels & Teeth	198
	7.6.5.2	Getting Good Compaction	199
	7.6.5.2.1	Compacting with Track-Type Tractors	199
	7.6.5.2.2	Compacting With Steel Wheeled Compactors	199
7.6.6		Optimizing the Compactor's Effort	200
	7.6.6.1	Costs	200
	7.6.6.2	Benefits	201
	7.6.6.3	Optimum Density	201
	7.6.6.4	Measuring Compaction	202
	7.6.6.4.1	Compaction Test Procedure	202
7.6.7		Trimming Refuse - Prep for Cover	204
7.7		Cover Soil	205
	7.7.1	Covering a Cell	205
	7.7.1.1	Cell Volume	205
	7.7.1.2	Cell Surface Area	205
7.7.2		Daily Cover	206
7.7.3		Alternative Daily Cover (ADC)	206
	7.7.3.1	Geosynthetic Blankets (Tarps)	206
	7.7.3.2	Green Waste	206
	7.7.3.3	Foams	208
	7.7.3.4	Other Materials	208
7.7.4		Intermediate Cover	209
7.7.5		Final Cover	209
	7.7.5.1	Base Layer	209
	7.7.5.2	Low-Permeability Layer	209
	7.7.5.3	Top Layer	209
7.7.6		Determining the Optimum Cover Ratio	209
7.7.7		Placing Cover Soil	210
	7.7.7.1	The Dozer's Role in Cover Placement	210
	7.7.7.2	Strip and Reuse Previously Placed Soil	210
7.7.8		Different Techniques for Various Soils	211
	7.7.8.1	Silts/ Loams/Weathered Shales	211
	7.7.8.2	Cohesive Soils/Clays	211
	7.7.8.3	Dry Sand/Loess	211
7.7.9		Excavating Cover Soil	211
	7.7.9.1	Maximizing Scraper Productivity	212
	7.7.9.1.1	Production Analysis	212

	7.7.9.1.1.1	Fast Operator	212
	7.7.9.1.1.2	Smart Operator	212
7.7.9.2		Optimum Payload (Load Growth Curve)	213
7.7.9.3		Cycle Times: Key to Productivity	213
	7.7.9.3.1	Laying Out the Scraper's Route	214
	7.7.9.3.1.1	Excavation Area	214
	7.7.9.3.1.2	Scraper's Haul Road	215
	7.7.9.3.1.3	Stockpile or Dump Area	215
	7.7.9.3.1.4	Guidelines for Self-loading Scrapers	215
	7.7.9.3.1.5	Guidelines for Push-loading Scrapers	215
7.7.10		Trucks and Excavators	216
	7.7.10.1	Introduction	216
	7.7.10.1.1	Economics	216
	7.7.10.1.2	Productivity	217
	7.7.10.1.3	Versatility	217
	7.7.10.2	Balancing the Truck/Excavator System	217
	7.7.10.3	Increasing the Productivity of Trucks	219
	7.7.10.3.1	Truck Bed Shape	219
	7.7.10.3.2	Truck Bed Size	219
	7.7.10.3.3	Tire Size	219
	7.7.10.3.4	Loading Position	219
	7.7.10.3.5	Dumping Pattern	219
	7.7.10.4	Increasing the Productivity of Excavators	219
	7.7.10.4.1	Bucket Size	220
	7.7.10.4.2	Bucket Shape	220
	7.7.10.4.3	Swing Time	221
	7.7.10.4.4	Cut Depth	221
	7.7.10.4.5	Loading Sequence	222
	7.7.10.5	When Are Trucks Best?	222
7.7.11		Minimizing Cover Soil Use	222
	7.7.11.1	Select Optimum Cell Geometry	222
	7.7.11.2	Build Cells Properly	223
	7.7.11.3	Finish Cells Properly	223
	7.7.11.4	Place Cover Soil with Dozer	223
	7.7.11.5	Use an Alternative Daily Cover	223
	7.7.11.6	Strip Available Soil Prior to Placing the Next Cell	223
	7.7.11.7	Prepare a Cover Soil Budget	223
7.7.12		Preparing and Monitoring a Cover Soil Budget	223
7.7.13		Soil Conversion Factors	224
	7.7.13.1	Units of Measurement	224
	7.7.13.1.1	Loose Cubic Yard	224
	7.7.13.1.2	Bank Cubic Yard	224
	7.7.13.1.3	Compacted Cubic Yard	225
	7.7.13.2	Soil Swell	225
	7.7.13.3	Soil Shrink	226
7.8		Environmental Controls	226
	7.8.1	Air Quality	227
	7.8.2	Odor Control	227
	7.8.2.1	Odor From Incoming Refuse	227
	7.8.2.2	Odors From In-place Refuse	227

7.8.2.3	Odors From a Leachate Evaporation Pond	227
7.8.3	Dust Control	227
7.8.3.1	Dust Palliatives	227
7.8.3.2	Speed Limits	228
7.8.3.3	Aggregate Gradation	228
7.8.4	Landfill Gas Control	228
7.8.5	Litter Control	228
7.8.5.1	Fencing	229
7.8.5.1.1	Fence Placement	229
7.8.5.1.2	Fence Alignment	230
7.8.5.1.3	Fence Height	231
7.8.5.1.4	Fencing Material	231
7.8.5.1.5	Fence Maintenance	231
7.8.5.2	Load Placement	231
7.8.5.3	Sheltered Filling Areas	231
7.8.5.4	Sticks, Bags, and Vacuum Trucks	232
7.8.5.5	Litter Travel Distance	232
7.8.6	Vector Control	233
7.8.6.1	Flies	233
7.8.6.2	Rats and Mice	233
7.8.6.3	Burrowing Pests	234
7.8.6.4	Feral Cats and Dogs	234
7.8.6.5	Birds	235
7.8.6.5.1	Bird Control Plan	235
7.8.6.5.1.1	Cover Soil Placement	235
7.8.6.5.1.2	Monofilament Line Shield	235
7.8.6.5.1.3	Anti-Perch Strips	235
7.8.6.5.1.4	Predator Decoys	236
7.8.6.5.1.5	Acoustic Controls	236
7.8.6.6	Other Vectors	236
7.8.7	Erosion Control	237
7.8.7.1	Slope Damage	237
7.8.7.2	Exposed Garbage	237
7.8.7.3	Downstream Sedimentation	238
7.8.7.4	Road Failure	238
7.8.7.5	Drainage System Failure	238
7.8.7.6	Destruction of Aquatic Habitat	238
7.9	How Climate Can Effect the Operation	238
7.9.1	Precipitation	238
7.9.2	Temperature Variations/Extremes	240
8.0	CONSTRUCTION PROJECTS	243
8.1	Road Building	243
8.1.1	Types of Road Construction	243
8.1.1.1	Temporary Roads	243
8.1.1.2	Permanent Roads	243
8.1.2	Clearing and Grubbing	244
8.1.3	Pioneering	244
8.1.4	Sloping	244
8.1.5	Blading	245

8.1.6	Road Surfacing	245
8.1.6.1	Gravel Road	245
8.1.6.1.1	Choker Drains	246
8.1.6.1.2	Gravel Design	246
8.1.6.2	Oiled Road	247
8.1.6.3	Chip Seal	247
8.1.6.4	Paving with Asphaltic Concrete (A.C.)	247
8.1.7	Road Maintenance	248
8.2	Clay Liners	249
8.2.1	Sub-grade	249
8.2.2	Clay Excavation	250
8.2.3	Spreading the Clay	250
8.2.4	Moisture Conditioning the Clay	251
8.2.5	Compacting	252
8.2.5.1	Self-propelled Sheepsfoot Compactors	254
8.2.5.2	Towed Sheepsfoot Compactors	254
8.3	Drainage Systems	255
8.3.1	Surface Drainage	255
8.3.1.1	Sheet Flow	255
8.3.1.2	Ditches	256
8.3.1.2.1	Ditch Design	256
8.3.1.3	Culverts	258
8.3.1.3.1	Culvert Design	258
8.3.1.4	Downdrains	259
8.3.1.5	Outlet Structures	259
8.3.1.5.1	Logs/Brush	259
8.3.1.5.2	Rocks/Riprap	260
8.3.1.5.3	Cast-in-Place Concrete	260
8.3.1.5.4	Pool of Water	260
8.3.1.6	Sedimentation Ponds	260
8.3.2	Sub-Surface Drains	262
8.3.2.1	Extraction-Type Sub-Surface Drains	262
8.3.2.1.1	Well Points	262
8.3.2.1.2	Sizing Drainage Material	263
8.3.2.2	Injection-Type Sub-Surface Drains	264
8.4	Dozer Operations	264
8.4.1	Clearing and Grubbing	264
8.4.1.1	Tree Removal	264
8.4.1.2	Removing Brush	265
8.4.2	Pioneering	265
8.4.3	Sloping	267
8.4.4	Pushing Garbage	267
8.4.5	Placing Cover Soil	267
8.4.6	Removing Rocks	268
8.4.7	Ripping	268
8.5	Motor Grader Operations	269
8.5.1	Ditching	270
8.5.2	Road Maintenance	272
8.5.3	Sloping	275

8.5.4	Finish Grading	276
8.6	Hiring a Contractor vs. Doing It In-House	276
8.6.1	Hiring a Contractor	276
8.6.1.1	Pros	276
8.6.1.1.1	Quality of Work	276
8.6.1.1.2	Minimal Equipment Costs	276
8.6.1.1.3	Productivity	276
8.6.1.1.4	Construction Timeline	276
8.6.1.1.5	Material Discounts	276
8.6.1.1.6	Work is Guaranteed	276
8.6.1.1.7	Minimum Drain on In-House Resources	277
8.6.1.1.8	Ability to Construct Multiple Projects	277
8.6.1.2	Cons	277
8.6.1.2.1	Higher Cost	277
8.6.1.2.2	Bidding Process	277
8.6.1.2.3	Doesn't Build In-House Experience	277
8.6.1.2.4	Construction Management	277
8.6.1.2.5	Construction Inspection	277
8.6.2	Doing the Work In-House	277
8.6.2.1	Pros	277
8.6.2.1.1	Convenience	278
8.6.2.1.2	Develop In-House Skills	278
8.6.2.1.3	Cost Savings	278
8.6.2.1.4	Eliminate Bidding Delays	278
8.6.2.2	Cons	278
8.6.2.2.1	Quality of Work	278
8.6.2.2.2	Strains In-House Resources	278
8.6.2.2.3	Hard to Manage Multiple Projects	278
8.6.2.2.4	Higher Material Costs	278
8.6.2.2.5	Decreased Productivity	279
8.6.2.2.6	Minimize Project Management	279
8.6.3	Comparing "TOTAL" Costs	279
9.0	SURVEYING	283
9.1	Introduction to Surveying	283
9.2	Surveying Equipment	284
9.2.1	Tripods	284
9.2.1.1	Levelling the Instrument	284
9.2.1.1.1	Four-Screw System	285
9.2.1.1.2	Three-Screw System	285
9.2.2	Construction Levels	285
9.2.3	Transits	286
9.2.4	Distance Measurement	287
9.2.4.1	Pacing	287
9.2.4.2	Measuring Wheels	287
9.2.4.3	Tape Measures	287
9.2.4.4	Optical Range Finders	288
9.2.4.5	Stadia Lines	288
9.2.4.6	Electronic Distance Meters	289
9.2.4.7	Coordinate Comparison	290

9.2.5	Hand Levels	290
9.2.5.1	Zeroing a Hand Level	292
9.2.5.2	Using a Boot	293
9.2.6	Abney Level	294
9.2.7	Miscellaneous Equipment	294
9.2.7.1	Compass	294
9.2.7.2	90 Degree Sight	296
9.2.7.3	Planimeter	296
9.2.8	Global Positioning System	296
9.2.8.1	Traditional Landfill Tasks	297
9.2.8.1.1	Topographic Mapping of Site	297
9.2.8.1.2	Survey Control/Grade Staking	297
9.2.8.1.3	Recording Location (X,Y,Z) of Special Wastes	297
9.2.8.1.4	Preparation of As-Built Plans	297
9.2.8.2	GPS - A Cost-Effective Alternative	297
9.2.8.2.1	Accuracy	297
9.2.8.2.2	Range Limitations	298
9.2.8.2.3	Dependability	298
9.2.8.3	The Landfill Surveying and Guidance System (LSGS)	298
9.2.8.3.1	Specific Landfill Application for The LSGS	298
9.2.8.3.1.1	Proximity Notification	298
9.2.8.3.1.2	Generation of Database (Topo Map)	299
9.2.8.3.1.3	Tagging Location of Special Features	299
9.2.8.3.2	Political and Economical Benefits of The LSGS	299
9.2.8.3.3	As-Built Plan Preparation	300
9.2.8.3.4	Guidance for Equipment Operators	300
9.2.8.3.5	Volume Calculations	300
9.2.8.3.6	Use as Traditional Surveying Tool	301
9.2.8.3.7	Recording Equipment Activities	301
9.3	Topographic Mapping	301
9.3.1	Aerial Photogrammetry	302
9.3.1.1	Benefits	303
9.3.1.1.1	General Accuracy	303
9.3.1.1.2	Cost	303
9.3.1.1.3	Photos	303
9.3.1.1.4	Surface Features	303
9.3.1.2	Drawbacks	303
9.3.1.2.1	Cost	303
9.3.1.2.2	Cannot Provide High Accuracy	303
9.3.2	Ground Surveys	303
9.3.2.1	Grid System	303
9.3.2.2	Mine Survey	303
9.3.2.3	Contour Method	304
9.3.3	Working with Topo Maps	305
9.3.3.1	Figuring Slope	305
9.3.3.2	Interpolating Between Contours	305
9.3.3.3	Sketching a Road Alignment	305
9.4	Construction Surveying & Staking	306
9.4.1	Stationing	306

9.4.2	Offset Stakes	307
9.4.3	Roads	307
9.4.4	Tipping Pads	308
9.4.5	Area Fills and Excavations	311
9.4.6	Liners and Final Cover	312
9.4.7	Drainage Structures	312
9.4.7.1	Example #1 - Sidehill Ditch	314
9.4.7.2	Example #2 - Roadside Ditch	314
9.4.7.3	Example #3 - Backhoe Ditch	316
9.5	TBM's and Reference Points	317
9.6	Checking Grade Using "Swedes" or Travellers	318
9.6.1	Sweding for Final Grade	318
9.6.2	Sweding a Ditch	319
9.6.3	Sweding a Road	319
9.7	Blue Tops	320
10.0	LANDFILL ECONOMICS	321
10.1	Typical Landfill Costs	321
10.2	Preparing a Landfill Operating Budget	322
10.2.1	Capital Costs	323
10.2.2	Operating Costs	323
10.2.3	Cost Units	323
10.2.3.1	Site Development Costs	324
10.2.3.2	Gatehouse/Collector	324
10.2.3.3	Pre-fill Stripping	326
10.2.3.3.1	Timing Method	326
10.2.3.3.2	Productivity Method	326
10.2.3.4	Refuse Handling	326
10.2.3.5	Daily Cover	328
10.2.3.6	Intermediate Cover	329
10.2.3.7	Final Cover	329
10.2.3.8	Security	330
10.2.3.9	Equipment Maintenance	331
10.2.3.10	Litter Control	332
10.2.3.11	Safety	333
10.2.3.12	Administration / Office	334
10.2.3.13	Drainage	336
10.2.3.14	Signs	336
10.2.3.15	Roads	337
10.2.3.16	Tipping Pads	337
10.2.3.17	Leachate Management	338
10.2.3.18	Methane Control	338
10.2.3.19	Landfill Expansion and Development	339
10.2.3.20	Hand Tools	340
10.2.3.21	Recycling / Composting	341
10.2.3.22	Closure / Post-Closure	342
10.2.3.23	Budget Summary	342
10.3	Valuing Landfill Airspace	344
10.3.1	Cost-Based Approach	344
10.3.2	Market-Based Approach	344

10.3.3	Factors Affecting the Value of Landfill Airspace	344
10.3.3.1	Remaining Life of Site	344
10.3.3.2	Local Economy	345
10.3.3.3	Incoming Tonnage	345
10.3.3.4	Ownership	345
10.3.3.5	Competition	345
10.3.3.6	Future Costs	345
10.4	Determining Cost of Materials, Labor, and Equipment	345
10.5	Calculating the Value of Landfill Airspace	346
11.0	LANDFILL SAFETY	347
11.1	Tractor Stability	347
11.1.1	Steepness of the Ground	347
11.1.2	Roughness of the Ground	347
11.1.3	Machine Speed	348
11.1.4	Machine Direction	348
11.2	Scavenging	348
11.3	Landfill Emergencies	349
11.3.1	Accidents	350
11.3.2	Fires	350
11.3.3	Hazardous Material Spills	351
11.3.4	Natural Disaster Response Plan	352
11.4	Hazardous Material Load Check Plan	352
11.5	Confined Space Entry Plan	353
11.6	Safety Meetings	354
11.7	Personal Protective Equipment	355
12.0	LANDFILL ADMINISTRATION	357
12.1	Recordkeeping	357
12.1.1	Subtitle D Records	357
12.1.2	Administrative Records	357
12.1.3	Operational Records	357
12.2	Establishing Standards	358
12.2.1	Employee Performance Standards	359
12.2.2	Safety Standards	359
12.2.3	Operating Standards	359
12.3	Data Tracking	359
12.3.1	Scale Database	360
12.3.2	Equipment Database	360
12.3.3	Electronic Equipment Monitoring	360
12.3.4	Machine Oil Sampling & Analysis	361
12.3.5	Refuse Density Database	361
12.4	Managing Employees	362
12.4.1	Leadership and Respect	362
12.4.2	Praise and Discipline	363
12.5	Overtime — Effect on Cost	363
12.5.1	Fixed Costs	363
12.5.1.1	Insurance	363
12.5.1.2	Sick Leave	364
12.5.1.3	Vacation	364

12.5.2	Variable Costs	364
12.5.2.1	Wages	364
12.5.2.2	Retirement Costs	364
12.5.2.3	Employment Taxes	364
12.5.3	Optimum Weekly Hours	365
12.5.4	Effect on Productivity	365
12.6	Establishing Tipping Fees	366
12.6.1	Charging by the Household	366
12.6.1.1	Pros	366
12.6.1.2	Cons	366
12.6.2	Charging by the Load	367
12.6.3	Charging by the Yard	367
12.6.4	Charging by the Ton	367
12.6.5	Recommended Method	367
12.6.6	Differential Rates for Hard-To-Handle Waste	368
12.6.6.1	Extra Cost to Handle	368
12.6.6.2	Extra Time to Handle	368
12.6.6.3	Value of Airspace Used	368
12.6.6.4	Market Based Costing for Hard-to-Handle Materials	369
12.7	Employee Training	369
12.7.1	Sample Training Agendas	370
12.7.1.1	Manager/Supervisor Training Agenda	370
12.7.1.2	Equipment Operator Training Agenda	370
12.7.1.3	Laborer Training Agenda	370
12.7.2	Training by Example	371
12.8	Working with the Local Enforcement Agency (LEA)	372
12.8.1	Snapshots of the Landfill	372
12.9	Site Inspections	374
12.10	Subcontracting the Landfill Operation	374
12.10.1	From the Contractor's Perspective	374
12.10.2	From the Owner's Perspective	375
12.10.2.1	Why Hire a Contractor	375
12.10.2.1.1	May Save Money	375
12.10.2.1.2	Avoid Liability	375
12.10.2.1.3	Minimize Staff Increases	375
12.10.2.1.4	Reduce Capital Costs	375
12.10.2.1.5	Provide Superior Service	376
12.10.2.1.6	Avoid Political Criticism	376
12.10.2.2	Why Not Hire a Contractor	376
12.10.2.2.1	May Cost More Money	376
12.10.2.2.2	Administrative Costs	376
12.10.2.2.3	Potential Liability	376
12.10.2.2.4	Build More Independence	376
12.10.3	The Contract Agreement	376
12.10.3.1	Define the Project	377
12.10.3.2	Length of Contract	377
12.10.3.3	Terms and Conditions	377
12.10.3.4	Establishing Minimum Standards	378
12.10.3.5	Checks and Balances	378

12.10.3.6	Contract Pricing	379
13.0	MONITORING SYSTEMS	381
13.1	Groundwater Monitoring	381
13.2	Surface Water Monitoring	382
13.3	Methane Gas Monitoring	383
13.3.1	Installing Methane Monitoring Systems	383
13.3.2	Collection of Methane Gas Samples	384
13.3.3	Measuring Methane Levels	384
13.3.3.1	Percent LEL	384
13.3.3.2	Percent by Volume	384
13.3.4	Climatic Conditions Which Can Affect Methane Concentrations	385
13.3.5	Migration of Methane Gas	385
13.3.6	Indicators of Methane Gas	386
13.4	Air Monitoring	386
13.5	Leachate Monitoring	386
14.0	COMPETITIVE LANDFILLS - DESIGNING FOR EFFICIENCY	387
14.1	Good Enough Isn't Good Enough Anymore	387
14.2	Re-Engineering Your Site for Increased Efficiency	387
14.2.1	Site Plan Review	387
14.2.1.1	Rerouting Utility Right-of-Way	387
14.2.1.2	Raising Final Grades	388
14.2.1.3	Lowering Base Grades	388
14.2.2	Operations Review	389
14.2.2.1	Water Truck Time Study	389
14.2.2.2	Collector Time Study	391
14.2.2.3	Dozer Time Study	391
14.3	Eliminating "Pride of Designership"	392
14.4	Don't Be a Goose	393
14.5	Simple Changes for Improving Efficiency	394
14.5.1	Adjust Landfill's Operating Hours	394
14.5.2	Work Compactor at "Optimum" Pace	394
14.5.2.1	Costs	394
14.5.2.2	Benefits	394
14.5.3	Finish Cell with "Good" Garbage	394
14.5.4	Monitor Cover Soil Placement	395
14.5.5	Post a Budget	395
14.5.6	Change Your Perspective	396
14.6	Secrets of the Pros	396
14.6.1	Creating Additional Airspace	397
14.6.1.1	Recompacting Garbage to Increase Density	397
14.6.1.2	Landfill Mining	398
14.6.1.3	Surcharging	398
14.6.1.4	Dynamic Densification	398
14.6.1.5	Building Steeper Perimeter Garbage Slopes	399
14.6.2	Excavating Old Garbage	400
14.6.2.1	Dozer	400

14.6.2.2	Scraper	401
14.6.2.3	Excavator	402
14.6.3	Increasing Production	402
14.6.3.1	Straight Pushes Are Best	402
14.6.3.2	Slot Dozing	402
14.6.3.3	Side-by-Side Dozing	403
14.6.3.4	Dozing Downhill	403
14.6.3.5	Tipping Pad Garbage Slide	404
APPENDIX A — Subtitle D Regulations		405
APPENDIX B — Emergency Response Plans		411
APPENDIX C — Resources		431
APPENDIX D — Landfill Forms		473
APPENDIX E — Math Tools		495
GLOSSARY		
Abbreviated Terms		505
Definitions		507
INDEX		511