

Contents

Page

Foreword	4
1 Scope	5
2 Normative references	5
3 Terms and definitions	5
4 Tasks for the manufacturer	8
4.1 Factory production control	8
4.1.1 Concept	8
4.1.2 Works' quality manual	8
4.1.3 Management systems	9
4.1.4 System of documentation	9
4.2 Internal quality control	10
4.2.1 Process control	10
4.2.2 Measuring and testing	10
4.2.3 Handling, storage, packaging and delivery	11
4.3 Autocontrol testing of samples	11
4.3.1 Sampling and testing	11
4.3.2 Corrective action	11
4.3.3 Measuring and test equipment for autocontrol testing	11
4.3.4 Quality records	12
5 Tasks for the certification body	12
5.1 General	12
5.2 Surveillance, assessment and acceptance of the production control	12
5.2.1 Inspection tasks	12
5.2.2 Frequency of inspections	12
5.2.3 Reports	12
5.3 Evaluation of the results of autocontrol testing of samples	12
5.3.1 Evaluation tasks	12
5.3.2 Number and timing of evaluations	13
5.3.3 Control period	13
5.3.4 Evaluation of test results	13
5.3.5 Reports	13
5.4 Audit testing of samples taken at the factory/depot and initial type testing	13
5.4.1 Sampling	13
5.4.2 Number of samples	13
5.4.3 Properties and test methods	13
5.4.4 Testing	14
5.4.5 Evaluation of test results	14
5.4.6 Reports	14
5.4.7 Proficiency testing	14
5.5 Initial inspection of the factory and the production control	14
5.5.1 Inspection of a new factory	14
5.5.2 Inspection of an existing factory	15
5.5.3 Criteria for the assessment of the production equipment	15
5.5.4 Criteria for the assessment of laboratories	15
5.5.5 Reports	15
5.6 Evaluation of test results during the initial period	15
5.6.1 Initial period	15
5.6.2 Evaluation of test results	16
5.6.3 Reports	16

6	Actions in the event of non-conformity	16
6.1	Actions to be taken by the manufacturer	16
6.2	Actions to be taken by the certification body	16
6.2.1	Following surveillance, assessment and acceptance of the production control (see 5.2) and evaluation of the results of autocontrol testing (see 5.3)	16
6.2.2	Following evaluation of the results of the audit testing of samples taken at the factory/depot (see 5.4 and Annex A)	16
7	Procedure for third party certification of conformity	17
8	Certificates of conformity and conformity mark	17
9	Requirements for dispatching centres	17
9.1	General requirements	17
9.2	Tasks for the intermediary	18
9.2.1	Measures to maintain the ground granulated blastfurnace slag quality	18
9.2.2	Confirmation autocontrol testing of samples taken at the dispatching centre	18
9.3	Tasks for the third party	18
9.3.1	Surveillance, assessment and acceptance of the measures to maintain the ground granulated blastfurnace slag quality and of the confirmation autocontrol	18
9.3.2	Audit testing of samples taken at the dispatching centre	19
9.3.3	Decisions to be taken	19
Annex A	(normative) Evaluation of the representativeness and the accuracy of the 28 day activity index test results	22
A.1	General	22
A.2	Sets of results considered	22
A.3	Evaluation procedure	22
A.3.1	Introduction	22
A.3.2	Symbols	22
A.3.3	Evaluation of whether set A and set B belong to the same population (sampling error check)	23
A.3.4	Comparison between set B and set C in order to check the accuracy of the autocontrol testing (testing error check)	23
Bibliography		24